

TASK ORDER # 52

**COUNTY OF LOS ALAMOS UTILITIES DEPARTMENT
PRICE AGREEMENT AGR16-044
PAUL PARKER CONSTRUCTION COMPANY
May 4, 2016**

PROJECT TITLE: TA-21 LANL ELECTRIC LINE EXTENSION

Trench and installation of 6" AND 4" Conduit with facilities for three phase power to TA21

The project is initiated by LANL (N3B) for the purpose of installing electric service to TA21.

Additional conduit and boxes for Fiber were also requested by LANL

Los Alamos County is requesting installation of three phase power to property along DP Road.

The trench will include 4" conduit for redundancy in service, the County will pay for the 4" conduit.

This page represents total costs for installation services.

LACU crews will supply and install conductors, switches and transformers.

Estimated Project Term: 25 Days from date of notice to proceed

1. Bid Item 82: Trench in soil (12" wide x 48" deep)..... 1500LF @ \$8.44/LF = \$12,660.00
2. Bid Item 79: Install 6" PVC..... 1500 @ \$2.32 /LF= \$3,480.00
3. Bid Item 78: Install 4" PVC..... 4500 @ \$1.32 /LF= \$5,940.00
4. Bid Item 98: 444 vault install.....4 @ \$1,318.41= \$5,273.64
5. Bid Item 123: Laborer...(Install Concrete).....8 hrs.@ \$44.30= \$354.4
6. Bid Item 122: foreman ... (Install Concrete).....8 hrs.@ \$63.28= \$506.24
7. Bid Item 123: Laborer...Install Rigid Elbows24hrs.@ \$44.30= \$1,063.20
8. Bid Item 95: Sleeve Pad install.....2@ \$632.84 = \$1,265.68
9. Bid Item 5: Potholing4 @ \$421.89= \$1,687.56
10. Bid Item 1: Pavement removal and replacement.....4050 sq. ft. @\$9.49 = \$38,434.50
11. Bid Item 96: Install manhole.....3 @ \$2,636.82 = \$7,910.46

TASK ORDER # 52

**COUNTY OF LOS ALAMOS UTILITIES DEPARTMENT
PRICE AGREEMENT AGR16-044
PAUL PARKER CONSTRUCTION COMPANY
May 4, 2016**

PROJECT TITLE: TA-21 LANL ELECTRIC LINE EXTENSION

Estimated Construction Cost: \$78,575.68

Contingency: \$7,000.00

Total \$85,575.68

Acceptance of Conditions and Items of Work

Department of Public Utilities: _____
Tim Glasco Date

Paul Parker Construction: _____
Brad Parker Date

Name: _____
Print