

Department of Public Utilities


Electric Distribution

Stephen Marez, P.E.

Electrical Engineering Manager







System Reliability

Systemic:

Overhead and Underground Failures

Non-Systemic:

Third Party Damage (Human Caused)

Animals

Weather

Trees


Unknown

SAIDI = SYSTEM AVERAGE INTERUPTION DURATION INDEX

The standard for measurement of system reliability according to IEEE

And APPA. Our benchmark for reliability is 60 minutes.





• SAIDI – System Average Interruption Duration Index

A measure of outage time per customer if all customers were out at the same time (hours per year)

SAIDI= (<u>Sum of all customer outage durations</u>)
(Total number of customers served)

System Management

- Perform System Analysis
- Utilize Milsoft/GIS interface for system model and mapping;
- Maintain protective device coordination
- Circuit configuration to provide redundancy
- New Los Alamos Switch Station for added redundancy
- Ensure GIS maps and Feeder 1-lines are up-to-date;
- Provide accurate switching procedures

FY20-21 ACHIEVEMENTS

- NM 502 NEW ELECTRIC DISTRIBUTION SYSTEM
- WHITE ROCK SUBSTATION SWITCHGEAR REPLACEMENT
- DP ROAD ELECTRIC LINE EXTENSION
- LASS CONDUCTOR INSTALLATIONS- 13T, 15T, 16T
- WHITE ROCK SUBSTATION FEEDER #3 INSTALLATION
- EL MIRADOR SUBDIVISION PHASE 1
- EXTENSIVE TREE TRIMMING EFFORTS
- POWER POLE REPLACEMENTS
- PHOTO VOLTAIC SYSTEM INSTALLATIONS

FY20-21 ACHIEVEMENTS

- SULLIVAN FIELD CLUBHOUSE
- NATURAL GROCERS
- AMI COLLECTOR INSTALLATIONS
- WHITE ROCK SPLASH PAD
- LA VISTA PRIMARY REPLACEMENT
- PAJARITO WELL PRIMARY REPLACEMENT

O&M GOALS

- CONTINUE WITH NO LOSS TIME ACCIDENTS
- COMPLETE THE CAPITAL PROJECTS THAT ARE SCHEDULED
- CONTINUE WITH THE ASSET MANAGEMENT PROGRAM
- CONTINUE WITH UG LIVE-FRONT TRANSFORMER REPLACEMENT PROGRAM
- CONTINUE INSPECTIONS AND MAINTENACE PROGRAM
- DEFINE AND DOCUMENT PROCEDURES

O&M GOALS

- MAINTAIN A SAIDI < 1 HOUR</p>
- MAINTAIN ACCURATE SYSTEM MAPS AND DRAWINGS
- STAY WITHIN BUDGET
- CONTINUE WITH THE UNDERGROUND POWER LINE SEGMENT REPLACEMENTS
- CONTINUE WITH OH POLE AND CROSS-ARM REPLACEMENT PROGRAM

CHALLENGES

- ELECTRICAL ENGINEERING STAFF PROVIDES DESIGN AND PROJECT MANAGEMENT OF ELECTRIC FACILITY INSTALLATIONS ON ALL COUNTY AND CUSTOMER DEVELOPMENTS
- INVENTORY SUPPLY CHAIN DELAYS OVER 20 WEEKS FOR MOST MATERIALS, CABLE, TRANSFORMERS, TERMINATONS, METERING EQUIPMENT.

CHALLENGES

 TIME SCHEDULE CONFLICTS BETWEEN OPERATIONS, CAPITAL PROJECTS AND COUNTY PROJECTS

METER MAINTENANCE IN THE NEW SYSTEM

 TYLER-MUNIS SYSTEM ASSET DATA ENTRY AND FINANCIAL DATA ACQUISITION.

ONGOING ACTION ITEMS

- TRAINING FOR LINEMEN AND ENGINEERING STAFF
- COMPLETE PREPERATION FOR LASS COMMISSIONING
- INSTALL THREE PHASE RECLOSERS WHERE NEEDED
- COMPLETE PROCEDURE DOCUMENTATION
- CONTINUE MILSOFT SYSTEM MODEL
- WORK WITH PROCURMENT ON LONG LEAD ITEMS
- AMI COMMERCIAL METERS-TESTING & INSTALLATION
- COMMISSION THE L.A. SWITCH STATION
- INSTALL CONDUCTORS FROM EAST JEMEZ ROAD TO DIAMOND DRIVE.

ACTIVE PROJECTS

- EL MIRADOR SUBDIVISION
- CHERYL AND CONNIE PRIMARY REPLACEMENT
- AMI COMMERCIAL METER TESTING AND INSTALLATIONS
- LASS SUBSTATION ACTIVATION
- LASS FEEDERS (CANYON CROSSING & DIAMOND)
- EA4 CIRCUIT REPLACEMENT DESIGN
- LOS PUEBLOS & TOTAVI REPLACEMENT DESIGN

ACTIVE PROJECTS

- THE HILLS SUBDIVISION
- PET PANGEA AND FINCH STREET
- EL VADO HYDRO PLANT TRANSFOMER
- ARKANSAS APARTMENTS
- MARRIOT HOTEL
- RIM TRAIL TUNNEL
- AQUATIC CENTER LEISURE LAGOON
- AIRPORT FUEL FARM
- STARBUCKS

ACTIVE PROJECTS

- CANYON WALK APARTMENTS
- THE BLUFFS APARTMENTS
- DP ROAD PHASE TWO UTILITY REPLACEMENT PROJECT
- CANYON ROAD APARTMENTS DESIGN
- RESIDENTIAL PV SYSTEM INSTALLATIONS
- TRACT A-16 DEVELOPMENT
- WHITE ROCK SEWER PLANT
- WHITE ROCK NON-POTABLE POND / PUMPS
- SKI HILL WATER PROJECT

LASS- LA SWITCH STATION



LASS- LA SWITCH STATION





LASS- NEW FEEDER CIRCUITS





WHITE ROCK SUBSTATION





FY22 CAPITAL PROJECTS BUDGET

DESCRIPTION BUDGET COST

OVERHEAD SYSTEM REPLACEMENTS

Poles, cross-arms, open secondary, etc.

White Rock	\$150,000 \$450,000
Los Alamos Subtotal OH	\$150,000 \$300,000

URD REPLACEMENTS

White Rock	\$200,000
Los Alamos	\$200,000
Subtotal UG	\$400,000

PRIORITY LIST PROJECTS

CIRCUIT-PRIORITY-RANK	DESCRIPTION
13-1-1	REPLACE SWITCHES SC1305A, SC1309 AND SC1309A
13-1-2	NEED TO REPLACE TRANSFORMERS 725 AND 726
14-1-1	REPLACE 15TH AND IRIS SWITCH SC1401A
14-1-2	REPLACE YMCA SWITCH SC1401A2
15-1-1	CHANGE OUT POLES AT ARKANSAS 3091,3093,3095,3098,3087,3095
15-1-2	REPLACE URD PRIMARY LINE FROM SYCAMORE TO PUEBLO COMPLEX
16-1-1	INSTALL PRIMARY J-BOXES AT 897 & 921 ESTATES DR.
16-1-2	REPLACE PRIMARY CABLE IN LA MESA RRAILER PARK
17-1-1	REPLACE POLE #6152
17-1-2	REPLACE POLE #6154
17-1-2	REPLACE POLE 6137
17-1-3	REPLACE POLE #6138
17-1-4	REPLACE POLE # 6143
17-1-5	REPLACE POLE #6144
17-1-6	REPLACE POLE #6034
17-1-7	REPLACE POLE #6011
17-1-8	REPLACE POLE #6002
17-1-9	REPLACE POLE #6037
18-1-1	REPLACE SWITCH SC1803
18-1-2	INSTALL TRANSFORMER PAD AT MERRICK -
18-1-3	REPLACE OPEN DELTA TRANSFORMERS AT DP ROAD
18-1-4	REMOVE TRANSFORMER 1101 FROM MAIN TIE TO 18 AT DP ROAD
EA4-1-1	REPLACE MULTIPLE POLES AND CROSSARMS
	DERIVACE ACCOUNT DUMOS DE MANON CUERNI CE CONTRUE
WR1-1-1	REPLACE 4000' 1-PHASE PRIMARY: CHERYL CT,CONNIE
WR1-1-2	REPLACE 4 PADMOUNT SWITCHES ON ARAGON AVE. WR1-3,WR3-2,WR3-3,WR3-4,WR3-5,WR3-6
WR1-1-3	CHANGE OUT TRANSFORMER P3631 AT DNCU MALL
WD2 4 4	COMPLICTOR REPLACEMENT LA CEMPA AND RIFERRA LOGR
WR2-1-1	CONDUCTOR REPLACEMENT LA SENDA AND PIEDRA LOOP
WR2-1-2	REPLACE CONDUCTOR VALLE DEL SOL

OVERHEAD MAINTENANCE







2 fiberglass X-arms






> OH maintenance will be ongoing until the entire system is replaced

Switches

- 168 Pad mount Switches
- Service Life Estimated @ 20 Years
- 6 remaining switches installed in the 1970's and 1980's
- They are prioritized for replacement
- Almost all switch replacements occur at night due to long outage requirements on major feeder sections.
 Switches are evaluated and replaced as listed in the priority list.





SWITCHES BY AGE AND CIRCUIT

	QUANTITY	PRIOR TO 2006	2006-2021
CIRCUIT 13	25	10	15
CIRCUIT 14	30	9	21
CIRCUIT 15	37	17	20
CIRCUIT 16	19	7	12
CIRCUIT 17	11	2	9
CIRCUIT 18	14	1	13
WHITE ROCK 1	11	9	2
WHITE ROCK 2	7		7
WHITE ROCK 3	5		5
EA4	3	1	2
BANDELIER	8		8
TOTAL	171	56	115

Transformers

- 217 Three Phase Transformers
 11% Over 30 Years Old
 Replacement Cost Approximately
 \$15,000 each
- 1294 Single Phase Transformers
 20% Over 30 years Old
 Replacement Cost Approximately
 \$2,000 each
- Service Life 25 to 40 Years
- LIVE FRONT TRANSFORMERS ARE REPLACED AS PART OF CAPITAL AND OPERATIONS ACTIVITIES. AL OTHERS ARE REPLACED WHEN FAILURE OCCURS

3-Phase Transformers by age and circuit

	QUANTITY	1980 - 1989	1990 - 1999	2000 - 2006	2006-2021
CIRCUIT 13	48	10	12	15	11
CIRCUIT 14	42	15	13	5	9
CIRCUIT 15	13		5	4	4
CIRCUIT 16	12		5	2	5
CIRCUIT 17	40	4	12	20	4
CIRCUIT 18	26	6	5	7	5
WHITE ROCK 1	16		4	8	4
WHITE ROCK 2	15		6	7	2
WHITE ROCK 3	0				
TOTAL	217	24	18	72	103

1- Phase Transformers by age and circuit

	QUANTITY	1980 - 1989	1990 - 1999	2000 - 2006	2006-2021
CIRCUIT 13	308	116	52	75	65
CIRCUIT 14	58	10	14	20	14
CIRCUIT 15	235	18	37	80	100
CIRCUIT 16	257	67	30	47	113
CIRCUIT 17	8				8
CIRCUIT 18	15			6	9
WHITE ROCK 1	188	25	43	49	71
WHITE ROCK 2	217	50	60	57	50
WHITE ROCK 3	8				8
TOTAL	1294	286	236	334	438





Power Poles

- 2386 Poles
- Inspected for Structural Integrity and Treated in 2006, 2013 and 2021
 - 286 Rejects (12%)
 - 160 Priority (7%)
 - Useful Life 6o+ Years if Treated in Regular Intervals

2006 Power Pole Study and Treatment By PMC (Pole Maintenance Company)

Results in 258 rejected poles being braced with steel to ensure integrity of each structure until replacement

2013 Power Pole Study and Treatment By Osmose

Results in the 28 rejected poles added to the list

2015 Power Pole Replacement Project By Elite Power and Recovery

Results in the replacement of 286 Power Poles
As part of the circuit 15 and 16 replacement Project

Newly awarded -2021 Power Pole Study and Treatment Project in process 20 rejected so far

2006 Power Pole Study

TABLE 3.3		Totals by Area				
				Considered	Percent of	
		Pole	Total	Priority of	Total	Percent Priority
Pole Series	Area	Count	Rejects	the Rejects	Rejects	Rejects
1000	Western Area	363	36	16	10%	4%
2000	Eastern Area	155	14	8	9%	5%
3000	North Community	656	60	39	9%	6%
4000	North Mesa	128	13	11	10%	9%
5000	Barranca Mesa	256	44	18	17%	7%
6000	White Rock	343	53	35	15%	10%
7000	Pajarito Acres	250	22	16	9%	6%
8000	Ski Hill	44	2	2	5%	5%
9000	S-18	191	26	15	14%	8%
Grand Totals		2386	270	160	11%	7%

Power Poles Replaced Since 2006









Pole Top Assemblies

- Inspected on an Annual Rotation
 by LACU Operations Staff to support
 AMT recommendations in preparation of the
 Annual Budget
- Goals: NESC Compliant Attachments
 Condition of Pole Assemblies
 Identify Attachments
 Structural Integrity of Crossarms
 and Equipment



Conductors

- Overhead 34% of Total
- Service Life Approximately 30 Years
- Underground 66% of Total
- UG Primary Cable Total 697,885' (per GIS 2021)
 - -In Conduit 72%
 - -Direct Bury 28%

Service Life Approximately 20 TO 30 Years Depending on installation method and type

Conductors install underground prior to 1980 are almost always direct buried or inserted in existing pipe.

Age of Overhead Conductors by Circuit

	1980 - 1989	1990 - 1999	2000 – 2006	2006-2021
CIRCUIT 13		20%		10%
CIRCUIT 14				
CIRCUIT 15		20%		80%
CIRCUIT 16	24%		25%	51%
CIRCUIT 17				
CIRCUIT 18				
WHITE ROCK 1	75%	10%	5%	
WHITE ROCK 2	85%	10%	5%	

Conductors are replaced as load increases in areas

PROJECT SUBDIVISION OR AREA	1 PHASE PRIMARY CABLE	3 PHASE PRIMARY CABLE	1 PHASE SECONDARY CABLE	YEAR INSTALLED
EASTERN AREA WEST OF CANYON ROAD	2821		11978	1978
TIMBER RIDGE, LOMA VISTA, RIDGEPARK, OPENNHEIMER	9724	17088	9506	1975-80
WESTERN AREA	9045	11349	20596	1980
RIDGEWAY, UPPER SANDIA, UPPER TRINITY, UPPER FAIRWAY	5447	16242	12009	2004
PONDEROSA ESTATES	7179	6828	5996	1992
LOS PUEBLOS NAVAJO	11079		20015	1978
BROADVIEW BIG ROCK LOOP LA MESA	25160	12813	23015	1980-90
LOMA LINDA	2410		4988	1980
QUEMAZON	31705	30570	23444	2001-3
NC1 NC2 BURNED AREA	37858	87063	53776	2004-5
DEER TRAIL	2406		1571	2000
TRINITY - DP ROAD TO 20TH		30972		2013
DEL NORTE DEL SOL SUBDIVISIONS	15495		13740	2006
ENTRADA PAJARITO CLIFFS		21792		2012-16
RIM ROAD QUARTZ	4044		9187	2018
SAN IDELFONSO TSANKAWI	11497	40149	12229	2014
EAST ROAD AIRPORT TO ENTRADA		18360		2017
NM502 PROJECT TEWA TO CENTRAL AND TRINITY	5200	12100		2020
DP ROAD PHASE 1	1100	5000		2021
CANYON ROAD NM502 TO 15TH	2821	9832		2006
DIAMOND DRIVE		32760		2007-9

137,185' PRIMARY UG CABLE INSTALLED PRIOR TO 2000 - 25% OF TOTAL 400,724' PRIMARY UG CABLE INSTALLED AFTER 2000 - 75% OF TOTAL

TOWNSITE CONTAINS 77% OF UG CABLE COUNTY WIDE

WHITE ROCK UNDERGROUND CABLE INSTALLATIONS (FEET)

1 PHASE PRIMARY CABLE	3 PHASE PRIMARY CABLE	1 PHASE SECONDARY CABLE	YEAR INSTALLED
10011		5697	2003-06
6500	13500	7200	2019-21
34666			1970
15462		10669	1970-76
16754		11954	1970
46661	16422	41280	1970-80
	10011 6500 34666 15462	PRIMARY CABLE 10011 6500 13500 34666 15462 16754	1 PHASE 3 PHASE SECONDARY CABLE PRIMARY CABLE CABLE 10011 5697 6500 13500 7200 34666 15462 10669

129,965' OF UG PRIMARY CABLE INSTALLED PRIOR TO 2000 - 81% OF TOTAL 30,011' OF UG PRIMARY CABLE INSTALLED AFTER 2000 - 19% OF TOTAL

WHITE ROCK CONTAINS 23% OF UNDERGROUND CABLE COUNTY WIDE

Estimated Cost of Replacements

PROJECT SUBDIVISION OR AREA	TRENCH LENGTH FEET	DIGGING CONDITIONS	YEAR INSTALLED	ESTIMATED COST OF REPLACEMENT	PROJECT DURATION	PRIORITY
LA SENDA PIEDRA LOOP	25000	BASALT	1970	\$2,500,000	2 YEAR PROJECT	1
LOS PUEBLOS NAVAJO	9500	HARD TUFFA	1978	\$1,400,000	1 YEAR PROJECT	2
LA VIST, SIERRA VISTA, PINION	8000	BASALT / FILL	1970-76	\$1,200,00	2 YEAR PROJECT	3
TIMBER RIDGE, LOMA VISTA, RIDGEPARK, OPENNHEIMER	4000	TUFFA / FILL	1975-80	\$600,000	1 YEAR PROJECT	4
RIDGECREST, HASTA LA VISTA	25000	BASALT / FILL	1970	\$2,500,000	2 YEAR PROJECT	5
EASTERN AREA WEST OF CANYON ROAD	4000	TUFFA / FILL	1978	\$400,000	1 YEAR PROJECT	6
ARAGON TO MEADOW LANE	46661	BASALT / FILL	1970-80	\$5,500,000	3 YEAR PROJECT	7
WESTERN AREA	9000	TUFFA / FILL	1980	\$700,000	2 YEAR PROJECT	8

TRENCH AND CONDUIT INSTALLATIONS
BY ON CALL CONTRACTORS. COSTS INCLUDE
PAVEMENT AND SIDEWALK REPAIRS.

Major UG issues to contend with in the future


■ Underground System

- Need to have the project funds to continue with URD replacement projects for SEGMENTS of the grid that we know will fail or have failed several times;
- The Los Pueblos, Navajo and Totavi power line will need to be replaced sometime in the near future; costs close to 1.4 million dollars

Los Pueblos, 5800ft of single phase (2 lines) replace due to numerous failures

Major UG issues to contend with in the future

The Pajarito Acres and La Senda underground electric conductors
Are old and direct buried. The area has had many failures and is in need
Of replacement. The area is generally basalt with difficult digging conditions.
The replacement of these conductors will take several years and should be
Initiated next year. Costs will be **over two million dollars** for the entire area
Installation of new conduit and conductors.



CABLE PULLING EQUIPMENT

THE CABLE PULLING MACHINE IS USED TO INSTALL UNDERGROUND CONDUCTORS AND THIS MACHINE IS FAILING.

MANAGEMENT AND FLEET ARE WORKING TOGETHER TO REPLACE THE MACHINE ONE YEAR IN ADVANCE OF THE SCHEDULED REPLACEMENT DATE. THE OVERALL COST FOR THE PULLER MACHINE WILL BE NEAR \$140,000.

THIS PIECE OF EQUIPMENT IS ESSENTIAL TO UNDERGROUND ELECTRIC OPERATIONS AND CAPITAL PROJECTS.


Major OH issues to contend with in the future

Overhead System

EA4 Feeder Replacement Project between PCS and Rendija Canyon may cost over \$2 Million.

This project could be split into smaller projects; for example, start with the Pueblo Canyon Crossing first.

The first phase should begin within 3 years;



Major OH issues to contend with in the future


- There are presently 60 pole structures
- Most are 2 or 3 pole H-type deadends (expensive)







- Proposed Design (< 20 pole H structures)
- Utilize transmission types structures to span the canyons



Manholes



Vaults and Junction Boxes



Delays in Electric Distribution system projects are due to the increased number of County and private projects.

The construction of homes and apartments did not slow down during COVID. Electric Distribution staff worked on site during the entire COVID pandemic and continue to constantly provide dependable service to our customers. No projects whether public or private are delayed due to Electric Distribution Department performance or material supplies.

This may change if the supply chain does not recover soon. The utility must maintain adequate reserves of materials for emergency outage response.

It is difficult to operate with 20+ week delays in product delivery.

The inflation of material prices is also making it difficult to accurately provide job cost estimates.

The utility supplies transformers, switches, conductor and vaults for all projects. The costs are passed along to the projects.

O&M PROJECTS

- COMPLETE PRIORITY ONE ITEMS FROM CONDITION ASSESSMENTS.
- THREE PHASE RECLOSER INSTALLATIONS
- POLE REPLACEMENTS ONGOING
- SWITCH REPLACMENTS ONGOING
- TRANSFORMER REPLACEMENTS ONGOING
- OUTAGE REPAIRS
- WHITE ROCK SUBSTATION HVAC UNITS AND THE UNIT 1 LOAD TAP CHANGER
- STATION METER DISPLAY REPLACEMENTS

BUDGET VARIANCES FY20

OPERATING EXPENSES	FY 2020 ADOPTED	FY 2020 ACTUAL	REMAINING BUDGET	% BUDGET
SUPERVISION, MISC. DIRECT				
ADMIN	607,254.25	145,774.25	461,480.00	24%
SUBSTATION MAINTENANCE	33,767.63	23,889.90	9,877.73	71%
SWITCHING STATION				
MAINTENANCE	52,716.77	5,753.32	46,963.45	11%
OVERHEAD MAINTENANCE	519,375.50	120,341.58	399,033.92	23%
UNDERGROUND MAINTENANCE	386,740.28	232,088.61	154,651.67	60%
METER MAINTENANCE	90,166.55	24,270.39	65,896.16	27%

BUDGET VARIANCES FY21

OPERATING EXPENSES	FY 2021	FY 2021	REMAINING	
As of May 2021	ADOPTED	ACTUAL	BUDGET	% BUDGET
SUPERVISION, MISC. DIRECT				
ADMIN	808,024.00	580,191.19	202,832.81	72%
SUBSTATION MAINTENANCE	66,724.00	6,387.18	60,336.82	10%
SWITCHING STATION				
MAINTENANCE	74,258.00	8,106.30	66,151.70	11%
OVERHEAD MAINTENANCE	547,372.00	390,865.28	156,506.72	71%
UNDERGROUND MAINTENANCE	521,802.00	479,781.10	42,020.90	92%
METER MAINTENANCE	275,062.00	120,188.17	154,873.83	44%

Org Name	FY21 Budget	YTD Actuals	Remaining Budget	% of Budget
SUBSTATION MAINTENANCE	66,724.00	6,387.18	60,336.82	10%
SWITCHING STATION MAINTENANCE	74,258.00	8,106.30	66,151.70	11%

THE SUBSTATION MAINTENACE BUDGET WAS SET UP TO FUND A NEW LOAD TAP CHANGER ON THE UNIT ONE TRANSFORMER. THE RESPONSE FROM THE VENDORS WAS STALLED BY COVID AND THE INABILITY TO FIND THE CORRECT PARTS FOR THE NEW LOAD TAP CHANGER. THE UNIT 2 TRANSFORMER SWITCH GEAR IS IN NEED OF AN HVAC UNIT FOR TEMPERATURE CONTROL.

THE BUDGET SHOULD REMAIN AT THIS LEVEL AND ENGINEERING WILL CONTINUE THE EFFORT TO OBTAIN THE LOAD TAP CHANGER AND HVAC UNIT

THE TOWNSITE SWITCHING STATION IS ALSO IN NEED OF HVAC FOR CLIMATE CONTROL.

Org Name	FY21 Budget	YTD Actuals	Remaining Budget	% of Budget
OVERHEAD MAINTENANCE	547,372.00	390,865.28	156,506.72	71%
UNDERGROUND MAINTENANCE	521,802.00	479,781.10	42,020.90	92%

THE MAINTENANCE OF OVERHEAD AND UNDERGROUND ELECTRIC FACILITIES IS ONGOING.

Org Name	FY21 Budget	YTD Actuals	Remaining Budget	% of Budget
METER MAINTENANCE	275,062.00	120,188.17	154,873.83	44%

THE MAINTENANCE OF COMMERCIAL METERING EQUIPMENT WILL ESCALATE THIS YEAR AS THE AMI PROJECT PROCEEDS. ENGINEERING WILL TEST AND DOCUMENT METER PERFORMANCE WITH THE OLD METER AND THEN WITH THE NEW METER. ANY REPAIRS THAT ARE NEEDED WILL BE PERFORMED. THE BUDGET LEVEL IS SUFFICIENT.

O&M PER ALL ACCOUNTS

	O&M Per All Accounts	APPA Mean Benchmark	Total O&M	Average # of Accounts
FY16	523.61	574.00	4,605,675.00	8796
			_	_
FY17	491.68	604.00	4,514,158.00	9181
FY18	698.43	655.00	6,700,061.00	9593
FY19	417.10	635.00	3,573,391.00	8561
FY20	272.14		2,384,518.00	8762
FY21	308.18		2,709,888.03	8793

Current Budget

The current annual capital budget for electric distribution is \$300k for overhead and \$400k for underground system replacements. This annual level of spending will adequately fund the in-house replacement of transformers, switches, poles and conductors. All replacements are prioritized through the asset management program.

Future Budget

The electric distribution system will require the replacement of direct buried and old conductors. The assessment provided, identifies the need for \$16 million over the next 14-year period. This includes the replacement of the EA-4 line which supplies primary power to the townsite water well system.

The reliability of the system is good. The multiple projects completed over the last decade have been focused on the three-phase primary backbone of the electric distribution system, both overhead and underground. The addition of the new Los Alamos Switch Station will further the reliability and redundancy of the system.

Over the last 20 years the conductors have been installed in conduit which allows for easier and cost-effective replacement in the future.

The current focus is on replacing the direct bury residential infrastructure in conduit.

Improvements to the electric distribution system are needed to meet DPU's goal of providing safe and reliable utility services.

QUESTIONS?